THE FEATHERSTONE BUILDING **Technical specification**

Technical specification

Occupancy		Grids				
Workplace density (NIA per workspace) Means of escape (NIA per person) Core elements (NIA per person) On floor services (NIA per workspace)	8 m ² 6 m ² 10 m ² 8 m ²	Planning grid Column grid		1.5 m x 1.5 m 6.0 m x 9.0 m		
, , , , , , , , , , , , , , , , , , , ,		Circulation				
Floor plate efficiency NIA:GIA		Percentage of primary circulation to NIA 20%				
Lower ground Ground First	28% 60% 86%	Toilet provision				
Second 87% Third 87% Fourth 86%	87% 87%	NIA per person Male/female ratio		8 m² (I:8) 60% / 60%		
Sixth	81%	Cycling provision & showers				
Seventh Eighth Ninth Tenth	81% 81% 81% 76%	202 secure cycle spaces 84 folding cycle spaces Shower facilities Male/female ratio Secure lockers		I per 7 staff I per 17 staff I per 60 staff 50% / 50% 0.7 per cycle space		
Plan depth & ceiling height				, ,		
Window to window Window to core	21 m 10 m – 13 m	Lifts				
Floor to ceiling height		4 passenger lifts Retail goods / accessible lift Loading bay goods lift	1100w x 140	400d x 2600h 00d x 2200h 00d x 2700h	1,600kg, 21 person 630kg, 8 person 2,000kg, 26 person	
Lower ground Ground Office floors (Ist – I0th)	2.625 m – 3.125 m 3.750 m 3.125 m	Car loading Waiting time (up-peak) Handling capacity (up-peak) Waiting time (two way lunchtin Handling capacity (two way lu NIA per person Hall call system: time to destine	inchtime)	80% 25 seconds 12% 35.2 seconds 13% 8 m ² < 80 seconds		

Raised floors		Comfort			
Typical floors	300 mm (overall)	Airtightness 3 m³/hr/m² Outdoor air I5 l/s Occupancy 8 m²			
Structural loadings		A			
Live: Office floors	3.5 kN/m²	———— Air conditioned space: Summer Winter	24° C +/- 2°C 21° C +/- 2°C		
Dead:		Mixed mode / natural vent:			
Partitions Loading bay Plant room Retail space	1.0 kN/m² 5.0 kN/m² 7.5 kN/m² 4.0 kN/m²	Summer Winter	24° C +/- 2°C 21° C +/- 2°C		
Floors, ceilings & services	0.85 kN/m ²	Noise criteria			
Small power		External noise intrusion: Open plan Speculative	NR38 (Leq) NR38 (Leq)		
Loading diversified on floor distribution Diversified load (1000 m²)	25W/m ² 25W/m ²	Cellular offices NR38 (Leq)			
		Sustainability			
Lighting		BREEAM	Acheived Outstanding		
Daylighting (target)	2%	LEED EPC	Targeting Platinum Achieved Rating 'A'		
Average maintained illuminance: VDU use	350-400 lux				
Unified glare rating (UGR) Electrical load allowance	19 12W/m²	Fibre	Fibre		
Lighting design load	7W/m ²	WiredScore	Platinum		

Technical specification

External finishes

Facade

- Robust brick piers with precast-concrete scalloped spandrel panels and central mullions in two colour palettes, light and dark brickwork
- Bronze finish curtain walling system with openable windows and bespoke channel detailing

Doors

- Glazed capsule doors to main entrance, with bespoke bronze finish channel detailing and curtain walling at high level
- Glazed aluminium door to other ground floor entrances with bespoke bronze finish channel detailing and curtain walling
- Full-height doors on office floorplates with bespoke bronze finish Juliette balcony balustrading
- Full-height metal doors to external terraces

Retail shell & core

Walls

- Exposed concrete surface, blockwork, and plasterboard walls

Concrete screed

Ceiling

Floors

Exposed concrete soffit

Doors

- Glazed aluminium doors to main entrance, with bespoke bronze finish channel detailing and curtain walling

Main reception area & café space

- External brickwork continues internally, with precast-concrete cladding at high level
- Exposed concrete structural beams
- White-painted acoustic plaster finish at high level and bespoke artwork by Hugo Dalton
- Oak timber cladding to rear wall with concealed doors
- Bronze finish curtain walling

Floors

- Warm-tone diamond polish concrete screed with exposed aggregate

Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits and sprinkler pipework

- Glazed capsule doors to main entrance, with bespoke bronze finish channel detailing and curtain walling at high level
- Glazed aluminium door to café entrance with bespoke bronze finish channel detailing and curtain walling

Reception desk

- Bronze finish expressive metal panels with fin detailing and diamond ground concrete surface

Office space

Walls

- Fair-faced concrete to core walls
- Bronze finish curtain walling with metal infill panels

Floors

- 600 x 600 mm fully accessible raised access floor

Ceilina

- Exposed concrete soffit
- Hanging lights and exposed conduits and sprinkler pipework

Doors

- Full-height office entrance doors with glazed vision panel

Concealed manual roller blinds

Core

Walls

Fair-faced concrete to core walls

Floors

Rough-sawn oak board flooring

Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits and sprinkler pipework

– Black powder-coated glazed doors, bathroom doors and riser access doors

Passenger lifts

Walls

- Black powder-coated expressive metal detailing and wall finish
- Mirror to rear, timber handrail

Floors

Oak board flooring

Ceiling

- Light box with perforated bronze finish metal panel below

Doors

- Black powder-coated metal doors

Stairs

Walls

- Fair-faced concrete

Floors

Polished concrete screed

Ceiling

- Exposed concrete soffit
- Hanging lights and exposed conduits

Doors

Black powder-coated glazed doors

Handrail

- Oak handrail

WCs

Walls

- White ceramic tiles with black metal trim
- Unpainted rough finish plaster to main space
- White painted plasterboard to cubicles

Floors

- Pattern ceramic tile

Ceiling

- Exposed concrete soffit to main space
- White painted plasterboard ceiling to cubicles
- Hanging and recessed lights and exposed conduits and ductwork

Doors

- Grey timber veneer finish doors to cubicles
- Black powder-coated bathroom doors to main space

Fixtures

- White floor standing ceramic WC pans, with black finish exposed wall mounted cistern
- Mahogany toilet seat
- Precast-concrete basins, black PVD coated taps and controls
- Undermounted black metal waste bin
- Black metal frame mirror
- Black PVD toilet roll holders, toilet brush, hooks, stops and ironmongery

Showers

Walls

- White ceramic tiles with black metal trim
- Unpainted rough finish plaster to changing-room space
- Full-height tiling to shower cubicles

Floors

- Pattern ceramic tile

Ceiling

- Exposed concrete soffit to changing-room space
- White painted plasterboard ceiling to shower cubicles
- Hanging and recessed lights and exposed conduits and ductwork

Doors

- Black laminate doors and side panels to cubicles
- Black powder-coated bathroom doors to main space

Fixtures

- Black metal and oak benches
- Precast-concrete basins, black PVD coated taps, showers and controls
- Undermounted black metal waste bin
- Black metal frame mirror
- Black PVD hooks, stops and ironmongery

Terraces

Finishes

- Bronze finish bespoke metal balustrading
- Precast-concrete paving slabs

Lighting

- Linear lighting at low level
- Wall mounted lighting along facade piers